



PROMIX Estimating Table

PROMIX Mortar <u>Type M-S-N</u>		
Units	Pieces per 70# Bag	Pieces per 3000# Bulk Bag
8x8x16 cmu	10	425
10x8x16 cmu	8	350
12x8x16 cmu	7	300
4 x 2 2/3 x 8 modular brick	30	1300-1500
3 x 3 1/5 x 9 5/8 king brick	20	900-1000
4 x 4 x 12 utility brick	16	750-850
PROMIX Masonry Cement <u>Mortar Mix</u>		
Units	Pieces per 70# Bag	Pieces per 3000# Bulk Bag
4 x 2 2/3 x 8 modular brick	33	1350-1600
3 x 3 1/5 x 9 5/8 king brick	25	925-1050
4 x 4 x 12 utility brick	20	775-900
PROMIX Core-fill <u>Masonry Grout</u>		
Units	Cores per 70# Bag	Cores Per 3000# Bulk Bag
8" Block (2 cores per unit)	4.50	200
12" Block (2 cores per unit)	3.25	140
PROMIX <u>Stone Veneer Products</u>		
70# PROMIX Stone Veneer Mortar	15 SQFT of Stone Placed	
70# PROMIX Stone Veneer Grout Mortar	20 SQFT @ 3/8" joint 15 SQFT @ 1/2" joint	
70# PROMIX Stone Veneer Scratch & Base	15 SQFT @ 3/8" joint 12 SQFT @ 1/2" Joint	
<i>*All Estimates are approximate and subject to finishing and material handling practices in the field.</i>		